

United States Department of the Interior  
National Park Service

See Attached SLR at bottom of Nomination.

National Register of Historic Places  
Registration Form

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in *Guidelines for Completing National Register Forms* (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets

(Form 10-200a) Type all entries.

## 1. Name of Property

historic name Paschall-Daniel House

other names/site number \_\_\_\_\_

## 2. Location

street & number 712 Raleigh Street☒ not for publicationcity, town Oxford☒ vicinitystate North Carolina code NCcounty Granvillecode 077zip code 27565

## 3. Classification

## Ownership of Property

- ☒ private  
☐ public-local  
☐ public-State  
☐ public-Federal

## Category of Property

- ☐ building(s)  
☒ district  
☐ site  
☐ structure  
☐ object

## Number of Resources within Property

Contributing	Noncontributing
<u>7</u>	<u>      </u> buildings
<u>1</u>	<u>      </u> sites
<u>2</u>	<u>      </u> structures
<u>      </u>	<u>      </u> objects
<u>10</u>	<u>0</u> Total

Name of related multiple property listing:

Historic & Architectural Resources of GranvilleNumber of contributing resources previously listed in the National Register 0County, N.C.

## 4. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act of 1966, as amended, I hereby certify that this ☐ nomination ☒ request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property ☒ meets ☐ does not meet the National Register criteria. ☐ See continuation sheet.

Signature of certifying official

Date

State Historic Preservation Officer

State or Federal agency and bureau

In my opinion, the property ☐ meets ☐ does not meet the National Register criteria. ☐ See continuation sheet.

Signature of commenting or other official

Date

State or Federal agency and bureau

## 5. National Park Service Certification

I, hereby, certify that this property is:

- ☐ entered in the National Register.  
☐ See continuation sheet.
- ☐ determined eligible for the National Register. ☐ See continuation sheet.
- ☐ determined not eligible for the National Register.
- ☐ removed from the National Register.
- ☐ other, (explain): \_\_\_\_\_

Signature of the Keeper

Date of Action

**6. Function or Use**

Historic Functions (enter categories from instructions)

Domestic-single dwelling

Agriculture/Subsistence

Current Functions (enter categories from instructions)

Vacant/not in use

**7. Description**

Architectural Classification

(enter categories from instructions)

Greek Revival

Materials (enter categories from instructions)

foundation brick

walls weatherboard

roof asphalt

other wood

Describe present and historic physical appearance.

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

Section number 7 Page 1 DESCRIPTION

The two-story, T-plan Paschall-Daniel House, probably raised by Dr. Zebulon M. Paschall between 1852 and 1858, is one of the most handsome, complete and intact Greek Revival style buildings in Oxford and Granville County. Now within Oxford's bounds, it originally stood to the south of the town, among other large mid-century residences, on the main road that connected the county seat with the state capitol. Though Raleigh Street is now interrupted by Interstate 85 to the south, and the nearby early residences are gone, the house still retains property sufficient to cultivate and to insulate it from much of the surrounding later development.

Built of mortised, tenoned and pegged timbers sheathed in beaded weatherboards, the house retains almost all of its original interior and exterior finish. The front porch that shades the three symmetrically placed bays of its first floor has six octagonal columns connected by octagonal handrails and thin "tobacco stick" railings. (Of the two ell porches, which may once have been one porch circling the entire rear elevation, only a side portion, enclosed in the 1950s, remains.) The windows that flank the deeply inset front entry have twelve-over-twelve sash, unusually substantial for the county, stretching virtually from floor to ceiling. When open, they provide such complete and easy access to the front porch that they are essentially transformed into doorways. Though not as long, the other windows are generously proportioned with eight-over-twelve sash downstairs and eight-over-eight above. Like the openings of the longer windows and the front entry, they are enframed by crossetted surrounds.

The most unusual feature of the exterior is found atop the low hipped roofs of the front block and two-story ell. Paired octagonal pots form the two interior chimneys of the front block, and similar pots, three in number rather than two, break through the center of the ell roof. These chimneys, a rare example of the Gothic Revival in antebellum Granville County residential architecture, are found at only one other nineteenth century residence in the county, the antebellum Titus Grandy House standing not a mile to the north near Oxford's center.

Both front block and rear ell are as finely finished inside as they are outside. The original raised two-panel doors, all of which are in place, are enframed by surrounds that reflect in their ornateness the hierarchy of the rooms, from private back

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

Section number 7 Page 2

---

bedroom to public front parlor, and from public downstairs to private upstairs. The central hallway downstairs and the transverse hall to its rear - divided into a bedroom and bathroom in the mid-1930s by the Daniels family - have fluted surrounds with bull's-eye cornerblocks, while the four bedrooms and hall upstairs, and the back bedroom downstairs, have plainer flat-angled surrounds. Fittingly, the two front parlors have the most ornate surrounds, fluted and framed by crossettes.

A similar hierarchy is found at the use of baseboards and wainscoting, indicating the favor the former had gained over the latter by mid-century. Flush-sheathed wainscoting adorns both the center front and transverse rear downstairs hallways, the downstairs back bedroom and three of the four upstairs bedrooms - the south rear bedroom, reduced in size in the mid-1930s by the addition of a small hall and bath, has no wall adornment. Simply molded baseboards adorn the upstairs hallway, while the fanciest baseboard treatment, tall elaborately molded boards, was reserved for the two parlors.

The dwelling's seven mantels match the number of exterior chimney pots. Mantels serve the four rooms of the front block, the rear bedroom downstairs and the north back bedroom upstairs. The seventh mantel is found in the basement sunk beneath the ell. (Though this basement, perhaps once a winter kitchen, underpins the ell, the main block simply rests upon a brick foundation.) Continuing the hierarchy of public position and importance of the rooms, the upstairs bedrooms have simple post and lintel mantels, while crossettes enframe the mantel of the downstairs rear bedroom and the south parlor. The north parlor has a heavy mantel with two freestanding columns probably added by Professor Buchanan early in the century. The overmantel of the other parlor mantel may also have been added around this time. Located on interior walls, the mantels are projected far out into the rooms, cutting down on floor space. This placement, however, provided a rare, mid-century bonus, for each mantel but that of the north parlor is flanked by a closet, each of which retains its original two-panel door.

By the time the Daniels bought the house ["A" on sketch map] in 1919 it had already had its original detached kitchen replaced by a late nineteenth century kitchen built at the southeast rear corner of the ell. Mr. Daniel erected a small frame milking house [D] to the rear of this kitchen to provide milk for the two



United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

Section number 7 Page 3

---

grocery stores he owned in Oxford. Extending his operation, he raised a small herd of dairy cattle in the fields behind the house and built a second, hipped roof, dairy processing building, which was turned into a tenant house in the 1960s [B]. Other outbuildings that apparently date from the Daniels tenure at the house include a frame garage [C], a frame barn [E], a frame milking barn [F] a frame wood house [G], a frame chicken house [H] and a log tobacco barn [I]. All of the outbuildings contribute to the integrity of the property. A large lawn and fields which are often cultivated also contribute to the integrity of the property.

-----

<sup>1</sup>An article by Ella C. Peace, the niece of the house's second owner, Willis Grandy, titled "Historical Sketch of Raleigh Road," was clipped from an unidentified newspaper of July 13, 1923, by Francis B. Hays and preserved at Volume 20 of his collection of scrapbooks. In an occasionally rambling fashion, it describes the "Interesting Places and People" of Raleigh Street.

Interview with Mrs. D. T. Broaddus, daughter of G. Norman and Manie(Talley) Daniel, September, 1986.

## 8. Statement of Significance

Certifying official has considered the significance of this property in relation to other properties:

☐ nationally ☐ statewide ☒ locally

Applicable National Register Criteria ☒ A ☐ B ☒ C ☐ D

Criteria Considerations (Exceptions) ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Areas of Significance (enter categories from instructions)

Architecture

Agriculture

Period of Significance

1850s-1937

Significant Dates

1850s

Cultural Affiliation

N/A

Significant Person

N/A

Architect/Builder

unknown

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.

☒ See continuation sheet

United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetSection number 8 Page 1 STATEMENT OF SIGNIFICANCE

---

Both inside and outside, the Paschall-Daniel House is architecturally significant as one of the most intact and striking examples of the Greek Revival style in Oxford. (See associated Property Type 2 - Greek Revival and Romantic Style Dwellings) Home to a number of wealthy individuals - it has changed hands many times in its history - the house represents gracious living in Oxford's environs both before and after the Civil War. (See Historic Contexts 1 - The Plantation Era in Granville County, 1746-1865 - and 3 - Bright Leaf Tobacco and the Ascendancy of Oxford, 1866-1937) With its eight outbuildings, it also gives a sense of the often rural nature of small town life in the county until well into the twentieth century. (See associated Property Type 6 - Outbuildings) Although the house and its position in the community have changed little since it was built, its period of significance is closed at 1937, because it has not achieved exceptional significance within the past 50 years.

The house was probably built by Dr. Zebulon M. Paschall (1812-1880) between 1852 and 1858. In 1850 he was living in Fishing Creek Township, south of the location of the house, with his wife, Eliza, and five children. The owner of 14 slaves, his estate was valued at \$3,000.00. In 1852 and 1853 he purchased three small tracts of land on Raleigh Road (now Raleigh Street) which, judging from their nominal purchase prices - \$600.13 3/4 for 18 3/4 acres - were likely undeveloped. In 1858, when he sold a six acre tract on the "west side" of the road "leading from the town of Oxford to Raleigh" to William J. Hamlet, he received the large sum of \$3,000.00, indicating that he had built a substantial house [Deed Book 20, Page 59].

Hamlet and attorney Marcellus V. Lanier sold the house the following year to Willis Grandy [Deed Book 20, Page 465]. In a 1923 newspaper sketch of Raleigh Road, Ella C. Peace wrote, "In 1859 my uncle, Mr. Willis Grandy, moved with his family from Camden county to Oxford to secure the benefit of good schools, and to enter into partnership in merchandizing with his brothers [sic], Titus G. Grandy."<sup>2</sup> According to the 1860 federal census the Grandys, both Willis and his wife Sarah, were quite wealthy. A 38 year old merchant, Titus' real estate was valued at \$7,000.00 and his personal estate at \$24,800.00; Sarah's personal estate was valued at \$22,800.00. The house they chose to purchase upon coming from the coast was fitting to their fortunes. The Grandys lived in the house until 1870; in that

United States Department of the Interior  
National Park Service

## National Register of Historic Places Continuation Sheet

Section number 8 Page 2

---

year they sold it, the first of more than nine transfers of the property in the next 35 years.<sup>3</sup>

In 1905 L. T. Buchanan purchased the house from S. V. Morton [Deed Book 59, Page 146]. A professor at Oxford College (the former Oxford Female Seminary), Buchanan probably added the heavy, columned mantel of the northeast parlor. He lived in the house until 1919, when he sold it to G. Norman and Manie (Talley) Daniel. Daniel owned two grocery stores in Oxford and one in Tar River. The house has remained in the Daniel family since, occupied first by the Daniels, then by their daughter and son-in-law, Virginia and L. L. Pettus.<sup>4</sup> Mrs. Pettus died in 1987 and the house is now in her estate.

The finish of the house was more than equal to its wealthy residents, for its Greek Revival motifs are as completely drawn as those of any building in the county. Outside, the windows are huge and enframed with crossettes; the octagon posts and rails of the front porch are intact; and the chimneys, also finished with octagons, are a rare surviving antebellum example of a Gothic Revival influenced motif. Inside the large, T-plan, two-story dwelling, the full panoply of Greek Revival style elements are also intact. The first floor adornment includes fluted bull's-eye cornerblock and crossetted surrounds, crossetted mantels and molded baseboards. Upstairs the post and lintel mantels, flush-sheathed wainscoting and flat-angled moldings are still in place. The placement of these elements - the most ornate in the public downstairs rooms, the least ornate in the downstairs rear and upstairs bedrooms - provides an excellent example of the hierarchy of rooms and public and private space in pre-Civil War dwellings in the county.

The outbuildings, all eight of which contribute to the integrity of the property, are also significant. In addition to indicating the rural nature of small town life in the county during the bright leaf era, they also speak of the activities of G. Norman Daniel. Daniel raised and milked his own cows on the property to provide dairy products for his three grocery stores. A former dairy processing building, now a tenant house, a former dairy house and a milking barn - all raised by him - still stand behind the house. Also behind the house are a chicken house, wood house, barn, garage and tobacco barn. Contributing fields, still often cultivated, and a yard still stand around the house, although Daniel's cows are now gone, along with the large

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

Section number 8 Page 3

---

vegetable garden that stood to the south of the house. Also gone are the rows of cotton to the north that were planted and tended by the Daniels' son, William. Though one rarely hears mention of cotton being grown in the county, William started to grow his for extra income while in high school and there was enough grown in the area early in the century to support a cotton gin that stood up Raleigh Street to the north.<sup>5</sup>

<sup>1</sup>In 1852 he purchased 7 1/4 acres of land on the "road leading from Oxford to Raleigh" for \$181.95 from Leslie Gilliam. In 1853 he purchased 4 3/4 acres of land on the "west side of Raleigh Road" from Jonathon Osborn for \$118.18 3/4. Also in 1853 he purchased an additional 6 3/8 acres of land on the west side of Raleigh Road from Rhodes N. Herndon for \$300.00.

<sup>2</sup>An article by Ella C. Peace, the niece of the house's second owner, Willis Grandy, titled "Historical Sketch of Raleigh Road" was clipped from an unidentified newspaper of July 13, 1923, by Francis B. Hays and preserved at Volume 20 of his collection of scrapbooks.

<sup>3</sup>In 1860 the Grandys sold the house, with 25 acres, to Thomas B. Venable [Deed Book 24, Page 343]. Venable sold it, also in 1870, to Dr. Samuel P. Waldo [Deed Book 25, Page 438]. In 1871, Dr. Waldo sold the house to Susan Bryan Williams, the wife of A. H. A. Williams [Deed Book 25, Page 480]. After an apparent break in the deeds, it was sold by L. C. Taylor, with 39 acres, to Archibald Taylor in 1874 [Deed Book 31, Page 546]. In 1887, on property reduced to 18 acres, Taylor's estate sold the house to Lettie K. Lassiter [Deed Book 41, Page 293]. Its property reduced back down to 6 acres again, the house was sold in the same year by R. W. Lassiter to C. A. Jenkins [Deed Book 44, Page 93]. In 1898 it was sold twice, first by Jenkins to Crawford J. Cooper [Deed Book 52, Page 231] and then by Cooper to Henry, Sue and Bettie Robards [Deed Book 52, Page 233]. No deed shows the transfer from the Robards, but in 1905 it was sold by S. V. Morton to L. T. Buchanan [Deed Book 59, Page 146].

The property must have long occupied a prime speculative position, for many of these individuals, including A. H. A. Williams, R. W. Lassiter and S. V. Morton, were among the town and county's major landowners.

United States Department of the Interior  
National Park Service

## National Register of Historic Places Continuation Sheet

Section number 8 Page 4

---

<sup>4</sup> Interview with Mrs. D. T. Broaddus, daughter of G. Norman and Manie (Talley) Daniel, September, 1986. According to G. Norman Daniel's account book, dated Jan. 1, 1920, the house cost \$8,000.

<sup>5</sup> Interview with Mrs. D. T. Broaddus, September, 1986.

Previous documentation on file (NPS):

☐ preliminary determination of individual listing (36 CFR 67)  
has been requested

☐ previously listed in the National Register

☐ previously determined eligible by the National Register

☐ designated a National Historic Landmark

☐ recorded by Historic American Buildings  
Survey # \_\_\_\_\_

☐ recorded by Historic American Engineering  
Record # \_\_\_\_\_

☒ See continuation sheet

Primary location of additional data:

☒ State historic preservation office

☐ Other State agency

☐ Federal agency

☐ Local government

☐ University

☐ Other


Specify repository:


## 10. Geographical Data

Acreage of property approximately 9 acres

## UTM References

C   

B   
Zone Easting Northing

D 

☒ See continuation sheet

### Verbal Boundary Description

☒ See continuation sheet

## Boundary Justification

☒ See continuation sheet

11. Form Prepared By

name/title Marvin Brown/Architectural Historian & Patricia Esperon/Historian  
organization Granville-Oxford Historic Survey date 12/9/78  
street & number P.O. Box 1556 (State Hist. Pres. Off.) telephone 919-693-1491  
city or town Oxford state N.C. zip code 27565

United States Department of the Interior  
National Park Service

# National Register of Historic Places Continuation Sheet

Section number 9 Page 1

## BIBLIOGRAPHY

Granville County Deeds. Granville County Courthouse, Oxford,  
N.C.

Granville County Wills. Granville County Courthouse, Oxford,  
N.C.

Hays, Francis B. Unpublished collection of 135 scrapbooks on  
Granville County history located at the Richard H. Thornton  
Public Library, Oxford, N.C.

"Historical Sketch of Raleigh Road." Unidentified newspaper  
(July 13, 1923). Article by Ella C. Peace, niece of house's  
second owner, Willis Grandy, preserved in the Hays  
Collection at Volume 20.

Interview, September, 1986, with Mrs. D. T. Broaddus - daughter  
of G. Norman and Manie (Talley) Daniel - who was raised in  
the house.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetSection number 10 Page 1

## GEOGRAPHICAL DATA

UTM REFERENCES

	Zone	Easting	Northing
A	17	717190	4019750
B	17	717090	4019910
C	17	717260	4020030
D	17	717300	4019960
E	17	717390	4020020
F	17	717450	4019930

VERBAL BOUNDARY DESCRIPTION

Beginning at point A: 17 717190 4019750 on the USGS polygon where the tree line meets the north side of Eighth Street, continuing in a straight line north, along the trees, approximately <sup>150</sup>600 feet to point B: 17 717090 4019910 on the polygon, where the trees turn east. Continuing in a straight line east, along the trees, approximately <sup>425</sup>525 feet to point C: 17 717260 4020030 on the polygon, where the tree line meets the field line. Continuing south, along the field line, approximately <sup>92</sup>150 feet to point D: 17 717300 4019960 on the polygon, where the field line turns east. Continuing east, along the field line, approximately <sup>280</sup>325 feet to point E: 17 717390 4020020 on the polygon, where the field line meets the western edge of Raleigh Street. Continuing south along the western edge of Raleigh Street, approximately <sup>300</sup>500 feet to point F: 17 717450 4019930 on the polygon, where the western edge of Raleigh Street intersects with the northern edge of Eighth Street. Continuing west along the northern edge of Eighth Street, approximately 850 feet to the point of origin. <sup>616</sup>

United States Department of the Interior  
National Park Service

## National Register of Historic Places Continuation Sheet

Section number 10 Page 2

---

### BOUNDARY JUSTIFICATION

Approximately 9 acres including the house, outbuildings and cultivated fields that have been historically associated with the property, maintain historic integrity, and convey the property's historic setting are being nominated for the National Register. The boundaries follow the owner's approximate property boundaries.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Continuation Sheet

Section number 10 Page 3 Paschall-Daniel House, Granville County, NC  
[p. 1 of amendment] [Amendment]

---

AMENDMENT TO GEOGRAPHICAL DATA


Granville County does not have tax maps. Consequently, when the nomination for the Paschall-Daniel House was prepared in 1987-88, the boundary of the nominated area, intended to be all of the parcel containing the house, was determined according to topographical landmarks and other information verbally described by the property owners. With this information, the nomination preparer drew boundaries on the USGS map and then wrote a verbal boundary description based upon the drawing and map scale.

In March, 1992, the current owners of the Paschall-Daniel House, who purchased the property in 1989, provided the State Historic Preservation Office of the North Carolina Division of Archives and History a copy of their deed of purchase, which includes a complete legal description of the property. The current owners purchased the entire parcel associated with the Paschall-Daniel House at the time of the nomination; the boundaries of that parcel have not changed nor have the buildings on the property been substantively altered beyond necessary repairs and sympathetic preservation work. In comparing the legal description to the nomination, discrepancies in the dimensions and acreage, attributed to the way in which the boundary had to be computed in 1988, were discovered. The acreage and verbal boundary description and justification which follow correct the 1988 nomination, which in all other respects remains accurate.

Amended Acreage: 7.17 acres

Amended Verbal Boundary Description: The nominated property is all of that parcel described in Granville County Deed Book 576, page 69.

Amended Verbal Boundary Justification: The boundaries encompass all of the property currently associated with the historic house and outbuildings. This property retains historic integrity and conveys the property's historic setting.



Contributing to the cultural field:


- H. 1st 1/3 of 20th century frame chicken house
- G. 1st 1/2 of 20th century frame wood house

Contributing Structure

PASCHALL-DANIEL HOUSE  
Granville County, N.C.  
Approximately 9 acres  
Approximate scale 1" = 150'

- Contributing Buildings
- A. mid-19th century building house
  - B. 1st 1/3 of 20th century frame house
  - C. 1st 1/3 of 20th century dairy processing buildings
  - D. 1st 1/3 of 20th century frame garage
  - E. 1st 1/3 of 20th century dairy house
  - F. 1st 1/3 of 20th century frame barn
  - G. 1st 1/3 of 20th century frame house
  - H. 1st 1/3 of 20th century frame house
  - I. 1st 1/3 of 20th century frame house

Underlined capital letters represent the order of the polygon drawn to encompass the property on the accompanying USGS map.



2000000 - Daniel House

Granville County, NC

Scale 1:24,000

17 717190 4019750  
17 717090 4019910  
17 717260 4020030  
17 717300 4019960  
17 717390 4020020  
17 717450 4019930

Central Orange

Granville County, N.C.

Quad. Oxford, N.C.

Scale 1:24,000 17'30"  
A 17 717950 4019040  
B 17 718050 4019020  
C 17 718000 4018900  
D 17 718000 4018800  
E 17 718040 4018950  
F 17 717970 4018930

920 000  
FEET





**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Continuation Sheet**

Section number SLR    Page \_\_\_\_\_

Paschell-Daniel House

Name of Property

Granville County, North Carolina

County and State

Granville County MPS

Name of multiple property listing (if applicable)

---

**SUPPLEMENTARY LISTING RECORD**

NRIS Reference Number: 88001263

Property Name: Paschell-Daniel House

County: Granville

State: NC

Date of Listing: 6/4/1992

This property is listed in the National Register of Historic Places in accordance with the attached nomination documentation subject to the following exceptions, exclusions, or amendments, notwithstanding the National Park Service certification included in the nomination documentation.

  
Signature of the Keeper

9/10/2025

Date of Action

---

Amended Items in Nomination:

The form for this property was marked "Not for Publication". After consultation with the North Carolina SHPO, it was determined that this was done in error.

The "Not for Publication" box is hereby unchecked and the file is no longer restricted.

---

The NC State Historic Preservation Office was notified of this amendment.

---

**DISTRIBUTION:**

**National Register property file**

**Nominating Authority (without nomination attachment)**